

March 27, 2019

CHP CR 193-12.62
ODOT PID# 98684

ADDENDUM #2

Please see the following pages for the Bid Form that was not included in the original Bid Package.

CHP CR 193-12.62

PID 98684

Bid Form

Line#	Item Number	Description	Quantity	Units	Unit Price	Extension
Group 1: Roadway						
1	201E11000	CLEARING AND GRUBBING	1.00	LS		
2	202E23000	PAVEMENT REMOVED	297.00	SY		
3	203E10000	EXCAVATION	115.00	CY		
4	204E10000	SUBGRADE COMPACTION	547.00	SY		
5	606E15050	GUARDRAIL, TYPE MGS	50.00	FT		
6	606E25550	ANCHOR ASSEMBLY, MGS TYPE A	4.00	EACH		
7	606E35002	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1 BARRIER REFLECTOR, TYPE 1	4.00	EACH		
8	626E00102	(BI-DIRECTIONAL)	8.00	EACH		
Total for Group 1:						
Group 2: Erosion Control						
9	659E10000	SEEDING AND MULCHING	350.00	SY		
10	832E30000	EROSION CONTROL	1000.00	EACH		
Total for Group 2:						
Group 3: Pavement						
11	304E20000	AGGREGATE BASE	183.00	CY		
12	407E10000	TACK COAT	60.00	GAL		
13	441E10000	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG64-22	87.00	CY		
Total for Group 3:						

Line#	Item Number	Description	Quantity	Units	Unit Price	Extension
Group 4: Traffic Control						
14	642E00100	EDGE LINE, 4", TYPE 1	0.20	MILE		
15	642E00300	CENTER LINE, TYPE 1	0.10	MILE		
Total for Group 4:						
Group 5: Bridge No. CHP-0193-1262						
16	202E11203	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	1.00	LS		
17	202E22900	APPROACH SLAB REMOVED	54.00	SY		
18	202E23500	WEARING COURSE REMOVED	376.00	SY		
19	407E10000	TACK COAT	48.00	GAL		
20	441E10100	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG70-22M	40.00	CY		
21	503E11100	COFFERDAMS AND EXCAVATION BRACING	1.00	LS		
22	503E21100	UNCLASSIFIED EXCAVATION	64.00	CY		
23	509E10000	EPOXY COATED REINFORCING STEEL	1454.00	LB		
24	509E20001	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL , AS PER PLAN	100.00	LB		
25	510E10000	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	48.00	EACH		
26	511E45710	CLASS QC1 CONCRETE, ABUTMENT	6.00	CY		
27	511E53012	CLASS QC2 CONCRETE, MISC. (INTEGRAL BACKWALL AND PIER DIAPHRAGM)	9.00	CY		
28	512E10100	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	210.00	SY		
29	512E33000	TYPE 2 WATERPROOFING	26.00	SY		
30	512E33010	TYPE 3 WATERPROOFING	323.00	SY		
31	515E10030	PRESTRESSED CONCRETE NON-COMPOSITE BOX BEAMS, B17-48 (39'-5" LENGTH)	18.00	EACH		
32	516E13600	1" PREFORMED EXPANSION JOINT FILLER	16.00	SF		
33	516E41100	1/8" PREFORMED BEARING PAD	36.00	EACH		
34	516E41500	1" ELASTOMERIC BEARING PAD	36.00	EACH		
35	517E70000	RAILING (TWIN STEEL TUBE)	247.00	FT		

Line#	Item Number	Description	Quantity	Units	Unit Price	Extension
36	518E21200	POROUS BACKFILL WITH GEOTEXTILE FABRIC	28.00	CY		
37	518E22300	SPECIAL - STEEL DRIP STRIP	293.00	FT		
38	518E40000	6" PERFORATED CORRUGATED PLASTIC PIPE 6" NON-PERFORATED CORRUGATED PLASTIC	70.00	FT		
39	518E40010	PIPE, INCLUDING SPECIAL S	40.00	FT		
40	519E11100	PATCHING CONCRETE STRUCTURE ROCK CHANNEL PROTECTION, TYPE C WITH	46.00	SF		
41	601E32200	FILTER	152.00	CY		
Total for Group 5:						

Group 6: Incidentals

42	614E11000	MAINTAINING TRAFFIC MAINTAINING TRAFFIC, MISC.	1.00	LS		
43	614E18002	(CANOE TRAFFIC) CONSTRUCTION LAYOUT STAKES AND	1.00	LS		
44	623E10000	SURVEYING	1.00	LS		
45	624E10000	MOBILIZATION	1.00	LS		
Total for Group 6:						

Engineers Estimate = \$500,000.00

Project Total

The undersigned, having full knowledge of the site, plans and specifications for the following improvement and conditions of this proposal hereby agrees to furnish all services, labor, material and equipment necessary to complete the entire project according to the plans specifications and completion dates, and to accept the unit prices specified for each item as full compensation for the work in the proposal.

Name: _____

Signature: _____

Title: _____

Phone: _____

Company: _____

Address: _____

Date: _____