

CHAMPAIGN COUNTY ENGINEER

428 Beech Street
URBANA, OHIO 43078

937-653-4848

Fax 937-653-3172

STEPHEN E. MCCALL P.E., P.S.
Engineer

Address Reply to
P.O. Box 669

June 6, 2018

Cable Road Paving

ADDENDUM #1

Correction to Specification #3 and corrected Bid Form:

ITEM 441 - ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (441), PG64-22, AS PER PLAN: Consists of placing and compacting 1 ½" of asphaltic concrete on Cable Road as shown within these specifications. The job mix formula shall be in accordance with **table 441.02-1 (PG 64-22) Type 1 Surface Course**. The provisions of 401.20 Asphalt Binder Price Adjustment will not be applied to these specifications.

Asphalt samples from each 1000 ton batch shall be taken throughout the application of the project. The Contractor will supply the necessary size plates (to be laid on the surface of the highway and paved over) for the samples and the Contractor will be responsible to take the sample and coordinate the collection of the samples with the County. All cost of testing shall be the responsibility of the County. All batch slips from the plant shall show the percent of AC asphalt contained in said load with all weight to be in "English" units (tons).

All butt joints will be required to be sealed with AC20. Only County and State roadways shall be utilized as haul roads unless otherwise approved by the Engineer in writing.

The average asphalt bitumen content shall be at least 6.2 % of the total mix per road. Test will be performed for every 500 tons laid. If an individual asphalt bitumen content test is below 6.0 % or above 8.0% the material shall be removed and replaced at the cost of the contractor.

Payment shall be based upon unit quantities applied as detailed in these specifications. The Contractor shall be paid 100% of all work performed, after test results of the asphalt samples have been determined to be in conformance.

Bid Form
2018 Cable Road Paving and Widening
Champaign County, Ohio

Item	Quantity	Unit	Description	Unit Price	Extension
1	735	Sq. Yd	Item 202- Wearing Course Removed		
2	203	Cu. Yd.	Item 411 - Stabilized Crushed Aggregate		
3	790	Cu. Yd.	Item 441 - Asphalt Concrete Surface 1 1/2" of Type 1 PG64-22		
4	1.33	Mile	Item 642 - Center Line		
5	2.65	Mile	Item 642 - Edge Line		
6	1	L.S.	Item 614 - Maintaining Traffic		
7	948	Gal	Item 407 - Tack Coat		
8	259	Cu. Yd.	Item 301 – Asphalt Base		
				Total	

I certify that I have inspected the job and have read and understand the plans and specifications, including the required completion date. Any questions or concerns about any quantities should be directed to the office of the Champaign County Engineer prior to submitting any bid.

By: _____

 Company: _____

 Address: _____

 Phone: _____
