

# **Champaign County Engineer**

428 Beech Street  
Urbana, Ohio 43078

**Stephen E. McCall P.E., P.S.**  
County Engineer

937-653-4848  
937-653-3172 fax

**Remit to Address**  
P.O. Box 669

## Runkle Road Paving 2021 Addendum 1

- The typical section on page 9 of the plans shows the 301 widening trench as 12" x 6". The correct dimensions for the widening trench should be 24" x 6". The calculations for the estimated quantities accurately reflect the 24" x 6" trench dimension.
- The County will plow out the widening trench prior to the placement of the 301 base by the contractor. The County will place barrels in the trench to protect the travelling public that can be removed to the ditch during the installation of the base material. The County will then pick up the barrels once widening has been completed. The contractor will need to coordinate this work with the County to keep the time that the widening ditch is open to a minimum for the safety of the travelling public.