

Champaign County Engineer

428 Beech Street
Urbana, Ohio 43078

Stephen E. McCall P.E., P.S.
County Engineer

937-653-4848
937-653-3172 fax

Remit to Address
P.O. Box 669

Brush Lake Road Paving 2021 Addendum 1

- The typical section on page 11 of the plans shows the 301 widening trench as 12" x 6". The correct dimensions for the widening trench should be 24" x 6". The calculations for the estimated quantities accurately reflect the 24" x 6" trench dimension.
- The County will plow out the widening trench prior to the placement of the 301 base by the contractor. The County will place barrels in the trench to protect the travelling public that can be removed to the ditch during the installation of the base material. The County will then pick up the barrels once widening has been completed. The contractor will need to coordinate this work with the County to keep the time that the widening ditch is open to a minimum for the safety of the travelling public.